

27-00000 INDEPENDENCE  
CONTROL

## ACTION



## 05-DOE-00593

[illegible]

COR. CONTROL	X	X
ADMIN. RECORD	X	X

Ref. Ltr. #


DOE ORDER #

5400.1


Sincerely,

**John J. Rampe, Director**  
**RFPO Closure Project Management**

cc w/o Encl.:  
F. Lockhart, OOM, RFPO  
D. Shelton, K-H  
B. Davis, K-H  
V. Moritz, USEPA



## ADMIN RECORD



**KAISER HILL COMPANY**

**LANDFILL MONITORING AND  
MAINTENANCE PLAN  
ROCKY FLATS ENVIRONMENTAL  
TECHNOLOGY SITE  
ORIGINAL LANDFILL**

**FINAL**

Project No. 57378.6040  
October 2005

EARTH  TECH  
A TETCO INTERNATIONAL LTD. COMPANY

---

**FINAL**  
**LANDFILL MONITORING AND MAINTENANCE PLAN**  
**ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE**  
**ORIGINAL LANDFILL**

*Prepared for:*  
Kaiser-Hill Company, L.L.C.  
Golden, Colorado

*Prepared by:*  
Earth Tech, Inc.  
Englewood, Colorado

Project No. 57378.6040

October 2005

---

## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
<b>LIST OF TABLES</b> .....	<b>iii</b>
<b>LIST OF FIGURES</b> .....	<b>iii</b>
<b>LIST OF APPENDICES</b> .....	<b>iii</b>
<b>LIST OF ACRONYMS AND ABBREVIATIONS</b> .....	<b>iv</b>
<b>1.0 INTRODUCTION</b> .....	<b>1-1</b>
1.1 PURPOSE.....	1-1
1.2 FACILITY LOCATION AND UNITS .....	1-1
1.3 SITE OPERATIONS.....	1-1
<b>2.0 SITE PHYSICAL DESCRIPTION</b> .....	<b>2-1</b>
2.1 TOPOGRAPHY .....	2-1
2.2 HYDROLOGY .....	2-1
2.3 CLIMATE AND PRECIPITATION .....	2-1
2.4 HYDROGEOLOGY.....	2-2
2.5 SITE FEATURES.....	2-2
2.5.1 Final Cover.....	2-2
2.5.2 Buttress Fill.....	2-3
2.5.3 Stormwater Management System .....	2-3
2.5.3.1 Introduction.....	2-3
2.5.3.2 Applications.....	2-3
2.5.3.3 Erosion Control.....	2-4
2.5.3.4 Run-on and Runoff Control .....	2-4
2.5.4 RCRA Groundwater Monitoring Network .....	2-4
2.5.5 Surface Water Monitoring.....	2-4
<b>3.0 FINAL COVER AND STORMWATER MANAGEMENT SYSTEM INSPECTION AND MONITORING</b> .....	<b>3-1</b>
3.1 INSPECTION PROCEDURES .....	3-1
3.2 SUBSIDENCE / CONSOLIDATION .....	3-1
3.2.1 Monitoring Locations and Procedures .....	3-2
3.2.2 Maintenance Action Activities.....	3-2
3.3 SLOPE STABILITY .....	3-2
3.3.1 Monitoring Locations and Procedures .....	3-3
3.3.2 Maintenance Action Activities.....	3-3
3.4 SOIL COVER.....	3-3
3.4.1 Monitoring Locations and Procedures .....	3-3
3.4.2 Maintenance Action Activities.....	3-4
3.5 VEGETATION.....	3-4
3.5.1 Monitoring Locations and Procedures .....	3-4
3.5.2 Maintenance Action Activities.....	3-5
3.6 STORMWATER MANAGEMENT STRUCTURES.....	3-5
3.6.1 Monitoring Locations and Procedures .....	3-6
3.6.2 Maintenance Action Activities.....	3-6
3.6.3 Institutional Controls.....	3-7
3.6.4 Condition of Monitoring Points .....	3-7
3.6.5 Site Conditions.....	3-7

	3.6.6 Reporting and Record Keeping.....	3-8
<b>4.0</b>	<b>GROUNDWATER MONITORING PLAN .....</b>	<b>4-1</b>
4.1	PURPOSE AND REQUIREMENTS .....	4-1
4.2	DATA QUALITY OBJECTIVES .....	4-1
4.3	WELL LOCATIONS.....	4-3
4.4	GROUNDWATER QUALITY SAMPLE PARAMETERS .....	4-3
4.5	SAMPLING PROCEDURES SUMMARY .....	4-3
	4.5.1 Groundwater Level Measurement.....	4-3
	4.5.2 Conventional Groundwater Purging and Sampling .....	4-4
	4.5.3 Quality Control Field Samples.....	4-4
	4.5.4 Decontamination .....	4-4
	4.5.5 Investigation-Derived Waste (IDW).....	4-4
4.6	LABORATORY PROCEDURES SUMMARY .....	4-4
4.7	DATA EVALUATION AND REPORTING .....	4-5
<b>5.0</b>	<b>SURFACE WATER MONITORING PLAN .....</b>	<b>5-1</b>
5.1	PURPOSE AND REQUIREMENTS .....	5-1
5.2	DATA QUALITY OBJECTIVES .....	5-1
5.3	SAMPLE LOCATIONS.....	5-3
5.4	SURFACE WATER SAMPLE PARAMETERS .....	5-3
5.5	SAMPLING PROCEDURES SUMMARY .....	5-3
5.6	LABORATORY PROCEDURES SUMMARY .....	5-4
5.7	REPORTING AND SCHEDULING.....	5-4
<b>6.0</b>	<b>REPORTING AND CONTACT INFORMATION.....</b>	<b>6-1</b>
6.1	REPORTING.....	6-1
6.2	CONTACT INFORMATION .....	6-1
<b>7.0</b>	<b>REFERENCES.....</b>	<b>7-1</b>

### LIST OF TABLES

<b><u>Table</u></b>	<b><u>Title</u></b>
4-1	Groundwater Monitoring Wells
4-2	Groundwater Sampling Parameters

### LIST OF FIGURES

<b><u>Figure</u></b>	<b><u>Title</u></b>
1-1	Location Map
1-2	Original Landfill Site Map
2-1	Original Landfill Cover
3-1	Original Landfill Stormwater Management Structure Details
4-1	Original Landfill Groundwater and Surface Water Monitoring

### LIST OF APPENDICES

<b><u>Appendix</u></b>	<b><u>Title</u></b>
A	Original Landfill – Monitoring and Maintenance Program Inspection Form
B	Groundwater Well Boring Logs / Construction Summaries

## LIST OF ACRONYMS AND ABBREVIATIONS

CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
DQO	data quality objective
EPA	Environmental Protection Agency
H	horizontal
IDW	investigation-derived waste
IM/IRA	Interim Measure/Interim Remedial Action
IMP	Integrated Monitoring Plan
Kaiser-Hill	Kaiser-Hill Company L.L.C.
LHSU	lower hydrostratigraphic unit
ml	milliliter
mph	miles per hour
OLF	Original Landfill
QA	quality assurance
QC	quality control
RCRA	Resource Conservation and Recovery Act
RFCA	Rocky Flats Cleanup Agreement
RFETS	Rocky Flats Environmental Technology Site
RL	reporting limit
SOP	Standard Operating Procedure
UHSU	upper hydrostratigraphic unit
V	vertical
VOC	volatile organic compound

## **1.0 INTRODUCTION**

### **1.1 PURPOSE**

This Monitoring and Maintenance Plan (Plan) has been prepared for the Original Landfill (Individual Hazardous Substance Site 115) at the Rocky Flats Environmental Technology Site (RFETS) and is designed to meet the following objectives:

1. Describe the procedures to be used to maintain the integrity and effectiveness of the final cover, including making repairs as necessary (Section 3.0);
2. Describe the features necessary to maintain and monitor the groundwater monitoring system (Section 4.0); and
3. Describe the features necessary to prevent run-on and runoff from eroding or otherwise damaging the final cover (Section 5.0).

Under the Final Interim Measure/Interim Remedial Action (IM/IRA) for the Original Landfill (Kaiser-Hill Company L.L.C. [Kaiser-Hill] 2005), a 2-foot-thick soil cover was selected to address closure of the Original Landfill. To enhance the slope stability of the landfill, the existing slopes were regraded prior to placement of the soil cover, and a buttress fill was installed at the toe of the landfill. The remedial action also included installation of perimeter drainage channels and cover diversion berms to control surface water run-on and runoff around the landfill cover. Construction was completed in September 2005, with the final regulatory walk-down occurring on September 12, 2005.

### **1.2 FACILITY LOCATION AND UNITS**

RFETS is a government-owned facility formerly used for the fabrication of miscellaneous weapons components for national defense. The 6,550-acre site is located in Jefferson County, Colorado, approximately 16 miles northwest of Denver (Figure 1-1). The Original Landfill is located south of the RFETS Industrial Area on a south-facing hill slope north of Woman Creek (Figure 1-2).

### **1.3 SITE OPERATIONS**

The Original Landfill was used to dispose of solid sanitary and construction debris wastes generated at the Rocky Flats Plant from 1952 to 1968 (Rockwell 1988). The landfill was not



designed or operated as an engineered landfill. Aerial photographs indicate that the landfill was operated as an area fill (EG&G 1994). Waste was merely dumped in the area vertically below and just south of the southern edge of the alluvial pediment on which the RFETS Industrial Area is located. The waste disposal area lies north of Woman Creek. The waste was generally spread over the south-facing hillside, serving to fill in the area below the pediment edge. No liner or other collection barrier was installed between the waste and the existing surfaces (Kaiser-Hill 2005). Additional information can be found in the IM/IRA for the Original Landfill (Kaiser-Hill 2005).

## 2.0 SITE PHYSICAL DESCRIPTION

This section describes the physical conditions at the Original Landfill site, such as topography, hydrology, climate and precipitation, hydrogeology, and site features, which include the final cover, the buttress fill, the stormwater management system, the Resource Conservation and Recovery Act (RCRA) groundwater monitoring network, and the surface water monitoring locations.

### 2.1 TOPOGRAPHY

The final topography of the Original Landfill is as shown on the post-construction survey (Figure 2-1). Slopes are as follows:

- Soil cover slope – 18 percent.
- Top of buttress fill slope – 2-5 percent.
- Buttress fill (south) sideslope – 3 horizontal (H):1 vertical (V)
- Perimeter channel sideslope – generally 3H:1V
- Perimeter channel slopes – approximately 12 percent

### 2.2 HYDROLOGY

The Original Landfill is located within the Woman Creek drainage. Diversion berms have been constructed on the soil cover to minimize surface water overland flow and divert run-on and run-off to the perimeter channels. The perimeter channels divert the surface water south of the landfill to below the buttress fill. Below the buttress fill, the perimeter channel slopes decrease, and flow encounters rock outfalls that dissipate the flow energy and allow the surface water to return to overland or sheet flow between the buttress fill and Woman Creek.

### 2.3 CLIMATE AND PRECIPITATION

RFETS is located in the southern Rocky Mountains and has a continental, semiarid climate. The region is noted for large seasonal temperature variations, occasional dramatic short-term temperature changes, and strong, gusty winds that reach 75 miles per hour (mph). Mean annual precipitation is approximately 15.5 inches, with approximately one-half of that amount occurring as snow.

## **2.4 HYDROGEOLOGY**

In the area of the Original Landfill, groundwater flows predominantly within the upper hydrostratigraphic unit (UHSU). The UHSU is composed of materials that include the quaternary Rocky Flats Alluvium, colluvium, Valley Fill Alluvium, and weathered claystone bedrock. Unweathered bedrock claystones are included as part of the lower hydrostratigraphic unit (LHSU). Groundwater elevations typically vary seasonally less than 5 feet, mostly in response to direct precipitation recharge in wetter periods and evapotranspiration in warmer months. Water levels above the weathered bedrock range from 0 to 5 feet along Woman Creek; below the bedrock in the east-central waste area; 5 to 10 feet in the central waste area; 0 to 5 feet in the western waste area; and from 10 to more than 40 feet above the bedrock north of the Original Landfill (Kaiser-Hill 2005).

Natural groundwater seeps were discovered during construction of the soil cover and perimeter channels. Several seeps were mitigated with a subsurface drain to the buttress sub-drain. The buttress sub-drain was constructed beneath the buttress fill to prevent buttress saturation. This drainage layer directs water to the south of the buttress into the Valley Fill Alluvium.

## **2.5 SITE FEATURES**

Site features included in the monitoring program at the Original Landfill include the final cover, the buttress fill, the stormwater management system, the RCRA groundwater monitoring network, and the surface water sampling locations. Construction included regrading of the site to consistent slopes. This included regrading the waste and placement of clean imported soil gradefill material. A minimum of 2-feet of Rocky Flats Alluvium soil cover was placed within the limit of waste. Monitoring procedures are provided in subsequent sections.

### **2.5.1 Final Cover**

The final cover of the Original Landfill includes a 2-foot-thick Rocky Flats Alluvium soil cover that was constructed over both the regraded surface and the buttress fill. The 2-foot-thick soil cover was constructed within the limit of waste and does not extend to the perimeter channels. Surface soil between the limit of waste and the perimeter channels is also Rocky Flats Alluvium, but was placed as regrade material.

Inspection and monitoring procedures to maintain the integrity and effectiveness of the final cover are included in Section 3.0.

## **2.5.2 Buttness Fill**

The buttness fill is an approximately 20-foot-high, 1,000-foot-long soil mass placed at the toe of the landfill (Figure 2-1). The compacted soil for the buttness fill was continuously tested for compaction and moisture content to meet design specifications. A sub-drain lies beneath the buttness fill and consists of drainage rock covered with a geotextile separation layer. The sub-drain is located below the surface and cannot be visually inspected. The buttness fill was constructed over the sub-drain with engineered fill compacted in 1-foot lifts.

## **2.5.3 Stormwater Management System**

### **2.5.3.1 Introduction**

The stormwater management plan is presented in Appendix D of the Original Landfill Design Submittal (Earth Tech, Inc. 2005). This appendix presents the results of calculations used to determine the stormwater run-on and runoff volumes to adequately design the diversion berms and perimeter channels. The stormwater management structures are designed to the 100-year, 24-hour storm event and include capacity to handle a 1,000-year, 24-hour storm event.

### **2.5.3.2 Applications**

Effective stormwater management is achieved in the system by applying the following principles:

- Protect the land surface from erosion (Section 2.5.3.3),
- Manage run-on and runoff (Section 2.5.3.4), and
- Inspect and maintain the erosion and stormwater management practices (discussed in Section 3.0).

In the long term, the system is designed as an erosion control system so sediment control will not be necessary since limited sediment will be generated. In the short term, sediment will be controlled with temporary erosion lining and check dams (GeoRidge®).

### **2.5.3.3 Erosion Control**

At the Original Landfill, stormwater management features have been designed with erosion control features to limit both short-term erosion and long-term erosion. Erosion control is any practice that protects soil surfaces and prevents the soil particles from being detached by rainfall or wind. Following construction, the soil cover was covered with both straw mulch and a spray-on erosion control medium called Flexterra™. The diversion berms and upper slope portions of the buttress fill are lined with temporary erosion mat. The diversion berms included temporary check dams (GeoRidge®) to limit sediment transport. These measures will limit short-term erosion until vegetation is established. The check dams may be removed at the end of the 2006 growing season if the vegetation is well established. The perimeter channels and lower sideslope of the buttress are lined with permanent erosion mat. Rock outfalls are present at the diversion berm outfalls to the perimeter channel outfalls to prevent scouring. All areas have been seeded to aid in long-term erosion protection.

### **2.5.3.4 Run-on and Runoff Control**

The stormwater management system is designed to collect, route, and discharge storm water run-on and runoff. Run-on stormwater is conveyed from upper portions of the Original Landfill as overland flow and then enters either the diversion berms or perimeter channels. Runoff enters the perimeter channel from overland flow on the cover and from the diversion berms constructed on the cover.

### **2.5.4 RCRA Groundwater Monitoring Network**

Four RCRA monitoring wells will be used for groundwater monitoring at the Original Landfill as discussed in Section 4.0. These wells will be monitored in accordance with the RFETS Integrated Monitoring Plan (IMP), FY2005 (Rocky Flats 2005). Of the four wells, one is upgradient and three are downgradient of the Original Landfill.

### **2.5.5 Surface Water Monitoring**

Surface water monitoring will be conducted at two locations, one upgradient and one downgradient of the Original Landfill. Sampling locations and procedures are discussed in Section 4.0.

During construction, intermittent seeps were discovered and remedied if necessary. Seep inspection is required and is discussed in Section 3.3.

### **3.0 FINAL COVER AND STORMWATER MANAGEMENT SYSTEM INSPECTION AND MONITORING**

This section outlines the inspection and monitoring program to be undertaken at the Original Landfill to ensure that the integrity of the cover is not compromised and continues to function as designed. Inspection and monitoring tasks will include monitoring subsidence/consolidation, slope stability, soil cover, vegetation, and stormwater management structures so that any potential maintenance actions can be taken in a timely manner.

#### **3.1 INSPECTION PROCEDURES**

In accordance with the IM/IRA (Kaiser-Hill 2005), site inspections of the area will be conducted on a quarterly basis following construction of the final cover, with the following exceptions:

- The site shall be inspected within two days after a storm event of one inch or more of rain in a 24-hour period,
- The site shall be inspected within two days after significant melt of a 10-inch or more snow storm assuming 10 inches of snow is equivalent to one inch of water, and
- The vegetation shall be inspected on a monthly basis from April to September and quarterly the rest of the year for the first two growing seasons following initial seeding (2006 and 2007).

Quarterly inspections will continue for five years and will be evaluated at the first Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) review.

Site inspections will be performed using a prescribed form containing a checklist of items that documents the evaluation of site conditions. The inspection form is included in Appendix A. The findings and observations of the site inspection will be entered on the form and presented in an Annual Original Landfill Monitoring Report. If deficiencies are discovered that require immediate attention, the Rocky Flats Cleanup Agreement (RFCA) parties will be notified.

#### **3.2 SUBSIDENCE / CONSOLIDATION**

Subsidence and consolidation at the Original Landfill largely depend on how well the waste was compacted when placed, thickness of the waste, age, and waste composition. Waste subsidence or continued consolidation may result in differential settlement, which generally occurs when

one area of waste settles more readily than another because of differences in waste composition, compaction, thickness, and moisture content. Differential settlement across the landfill may create cracks on the surface, which would allow precipitation to infiltrate more easily. Differential settlement can also change the topography of the landfill and create areas on the surface where ponding of water can occur. Localized waste subsidence can manifest itself in the form of cracks, depressions, and sinkholes. Construction of the final cover system included placement of engineered fills. Therefore, cover subsidence or consolidation is less of a concern than is waste subsidence.

### **3.2.1 Monitoring Locations and Procedures**

Subsidence/consolidation at the Original Landfill will be monitored by visually inspecting the entire surface of the landfill cover for cracks, depressions, and sinkholes on a quarterly basis. Visual inspections will involve traversing the landfill to gain perspective on regions of the landfill, i.e., every square foot of the landfill is not traversed. In addition, the seven diversion berm flow lines will be traversed to look for sloughing or differential settling that could change the flow line slope or berm height.

### **3.2.2 Maintenance Action Activities**

If differential settlement or localized subsidence appears to be substantial and likely to influence the integrity of the existing cover and surface water drainage over the Original Landfill, the RFCA parties will be consulted and maintenance actions may be taken to mitigate these concerns (e.g. areas of ponding water on the cover). Maintenance actions may include, but not be limited to, regrading the affected area to eliminate ponding and/or correct the slope of the surface. A maintenance action plan will be prepared, and the RFCA parties will be consulted prior to any action.

## **3.3 SLOPE STABILITY**

A landfill site may be susceptible to instability due to lateral movement. Slope failures can be caused by the weight of the wastes and cover material, steeply regraded slopes, and seepage forces resulting from water infiltration. Seismic forces can also cause slope failures. Steep slopes produce less stable conditions and are more susceptible to failure. Slope failures can also occur within the waste mass, resulting in downslope sliding of the cover components. The cover



system with buttress fill has been designed and constructed with applicable safety factors to guard against slope failure. Nevertheless, slope stability will be monitored.

### **3.3.1 Monitoring Locations and Procedures**

Slope stability at the Original Landfill will be monitored by visually inspecting the cover, the perimeter channel sideslopes, and the buttress fill sideslope slope for signs of cracks, evidence of block failure, seeps, and evidence of rotational failure. Visual inspection will involve traversing the slope to gain a perspective of the entire slope.

### **3.3.2 Maintenance Action Activities**

Based on the site monitoring data and consultation with RFCA parties, maintenance actions may be taken to address any potential slope stability failure at the site. The maintenance actions will include, but not be limited to, regrading affected areas, filling areas, maintaining positive drainage of surface water, seep drain construction, and regrading steep sections to achieve side slopes no greater than 4H:1V. A maintenance action plan will be prepared, and the RFCA parties will be consulted prior to any action.

## **3.4 SOIL COVER**

The cover system at the Original Landfill is designed to meet the minimum soil erosion requirements from both water and wind erosion. During the post-closure period, it is important to ensure that both temporary and permanent erosion controls are functioning properly. Regardless, the soil cover thickness may change over time due to wind and water erosion. Subsidence due to waste settlement and lateral movement of wastes or slopes may also contribute to changes in differential soil cover thickness.

### **3.4.1 Monitoring Locations and Procedures**

Monitoring of the soil cover at the Original Landfill will include the following:

- Visually inspecting the soil cover for erosion or deposition areas on a quarterly basis; and
- Visually inspecting the soil cover for signs of burrowing animals on a quarterly basis.

Visual inspection will involve traversing the slope to gain a perspective of the entire area.

### **3.4.2 Maintenance Action Activities**

If monitoring indicates significant loss of soil over time, the RFCA parties will be consulted and maintenance actions may be taken. Maintenance action will include, but not be limited to additional soil placement and regrading the affected areas to maintain the minimum design soil cover thickness and removing and relocating eroded soils (if necessary). The regraded areas will be vegetated per design criteria to prevent further erosion. Erosion control measures may be implemented to prevent further erosion of cover soils, (e.g., erosion control mat, revegetation), if necessary. A maintenance action plan will be prepared, and the RFCA parties will be consulted prior to any action.

## **3.5 VEGETATION**

Vegetation is important to long-term erosion protection for the cover, the upper portion of the buttress sideslope, and the diversion berms. Permanent erosion mat has been placed in the perimeter channels and the lower portion of the buttress sideslope; nevertheless, vegetation is important to reinforcing the erosion mat and providing long-term protection. For short-term protection, Flexterra and crimped straw have been placed on the cover, and temporary erosion mat, which has a 2 to 3 year life span, has been placed on the diversion berms and upper buttress fill sideslope. In addition, check dams have been placed in the diversion berms. Vegetation inspections will ensure that vegetation is established properly.

### **3.5.1 Monitoring Locations and Procedures**

The vegetation at the Original Landfill will be monitored by visual inspection on a monthly basis from April to September and quarterly for the rest of the year for the first two growing seasons following initial seeding (2006 and 2007), and only quarterly after that. Monthly inspections will help identify problematic weeds that can grow quickly and potential drought conditions that can adversely affect young vegetation. The vegetation will be monitored by traversing the cover and visually inspecting for the health of the grasses and for unwanted vegetation such as weeds or deep-rooting trees. The percentage of weeds versus grass on the cover will be estimated. At least one of the inspections during the spring/summer months must be conducted by a competent person capable of identifying weed species known in the area. If, after the first growing season, the Flexterra and mulch have eroded and vegetation is sparse, maintenance action will be necessary on the cover. If, after two growing seasons, the temporary erosion mat in the diversion

berms and upper buttress fill sideslope has degraded and vegetation is sparse, maintenance action will also be necessary.

### **3.5.2 Maintenance Action Activities**

If visual inspections indicate vegetation concerns on the cover, the RFCA parties will be consulted and maintenance actions may be taken. Actions may include, but not be limited to the following:

- Localized reseeded of the soil cover,
- Spot herbicide applications,
- Reseeding,
- Reapplication of temporary erosion controls,
- Removal of deep-rooting trees and repair of the area, and
- Planting willows in wet (seep) areas.

A maintenance action plan will be prepared, and the RFCA parties will be consulted prior to any action.

## **3.6 STORMWATER MANAGEMENT STRUCTURES**

Stormwater management inspections will be required on a quarterly basis at the Original Landfill to ensure that existing stormwater control structures (man-made drainage features) are functioning adequately to achieve the following objectives:

- Reduce flow onto the landfill (run-on controls),
- Reduce overland flow on the landfill,
- Collection and transport of runoff from the Original Landfill, and
- Limit transport of sediment from the disturbed areas to off-site drainage ways.

Existing stormwater controls at the Original Landfill include the following (Figure 2-1):

- Diversion berms 1 through 7,
- Diversion berm outfalls 1 through 7,
- Diversion berm temporary check dams (GeoRidge<sup>®</sup>),
- West perimeter channel,
- East perimeter channel,

- West perimeter channel outfall,
- East perimeter channel outfall,
- Permanent erosion mat-lined lower buttress fill sideslope,
- Vegetation/temporary erosion mat-lined upper buttress fill sideslope, and
- Temporary, naturally degradable, straw waddles between the diversion berms for additional erosion control.

Details of each type of structure are included on Figure 3-1.

### **3.6.1 Monitoring Locations and Procedures**

Stormwater management structures will be monitored visually by walking the structures and examining all components. Problem areas will be noted on the inspection form, graphically depicted, and photographed. At a minimum, these structures will be inspected for signs of excessive erosion, settlement, bank failure, breaches in the diversion berms, subsidence, burrowing animals, and blockage. Signs of potential problems include, but are not limited to, ponding water, gullying, sediment build-up, and depressions.

The perimeter channel lining and temporary diversion berm lining will be inspected for evidence of damage, displacement, undermining, scour, or deterioration. Repairs shall be made to re-stabilize the channel in accordance with the design specifications. Permanent and temporary erosion control mat lining on the buttress fill sideslope will also be inspected. The erosion control mat will be inspected for holes, rips, and separation. In addition, any evidence of erosion rills or gullies will be monitored during the inspection. The temporary check dams placed perpendicular to the flow lines of the berms will be inspected for excessive sediment and removed after vegetation is established. Riprap in the diversion berm and perimeter channel outfalls will be inspected for integrity and excessive sediment.

### **3.6.2 Maintenance Action Activities**

If the inspections indicate that the existing stormwater management structures are not adequately controlling surface water run-on and runoff, RFCA parties will be consulted and maintenance actions may be taken.

Routine maintenance of the surface water controls may include removing any blockages, filling eroded areas, replacing erosion control mat, or repairing other disturbances as necessary. Sediment may be removed periodically from the stormwater management structures to restore the design characteristics of the structure. Areas that exhibit excessive erosion may require placement of erosion control material or strengthening of the existing erosion control measures. A maintenance action plan will be prepared, and the RFCA parties will be consulted prior to any action.

### **3.6.3 Institutional Controls**

Institutional controls are used to control access and restrict activities at the Original Landfill to ensure the effectiveness of the engineered controls and the monitoring systems. Inspection at the Present Landfill will look for evidence that violate the institutional controls or damage the physical controls. On a quarterly basis, an inspection will be conducted to look for evidence of the following activities:

- Excavation(s) of the cover and in the immediate vicinity of the cover,
- Construction of roads, trails or buildings on the cover,
- Drilling of wells or use of groundwater for any purpose other than the accelerated action,
- Disruption or damage of the seep treatment system, and
- Damage or removal of any signage or groundwater monitoring wells at the Original Landfill.

A checklist of these items is included on the inspection form found in Appendix A.

### **3.6.4 Condition of Monitoring Points**

All established monitoring locations, such as groundwater wells, will be evaluated for ongoing integrity. The inspection will include documentation of any damage to the monitoring points that would impact their usefulness for inspections.

### **3.6.5 Site Conditions**

During site inspections, signs, markers, and the overall condition of the Original Landfill site will be checked to determine continuing effectiveness of institutional and physical controls.

### **3.6.6 Reporting and Record Keeping**

Inspection reports and findings will be included in the Annual Original Landfill Monitoring Reports discussed in Section 6.0. These annual reports will be submitted to the EPA and the Colorado Department of Public Health and Environment (CDPHE).

## **4.0 GROUNDWATER MONITORING PLAN**


This section presents the groundwater monitoring plan for the Original Landfill during the post-closure period. The plan establishes consistent monitoring locations and frequencies for the monitoring period.

### **4.1 PURPOSE AND REQUIREMENTS**

The Original Landfill groundwater monitoring plan has been implemented to determine groundwater quality impacts of the landfill (IM/IRA [Kaiser-Hill 2005]). The groundwater monitoring system was implemented under the IMP (Rocky Flats 2004) in accordance with 6 Code of Colorado Regulations 1007-3, 265.90[d]. The groundwater monitoring will be used to evaluate upgradient versus downgradient groundwater quality at the Original Landfill. Downgradient groundwater will also be compared to surface water standards (RFCA Attachment 5, Table 1).

### **4.2 DATA QUALITY OBJECTIVES**

Detailed data quality objective (DQO) information can be found in Section 3.3 of the IMP. Groundwater monitoring wells at the Original Landfill are categorized as RCRA monitoring wells under the IMP and undergo a certain decision statement, as outlined in Section 3.3.10.7 of the IMP. The following flowchart will be used to guide the decision statement:





### **4.3 WELL LOCATIONS**

Well locations have been chosen in compliance with the IMP (Rocky Flats 2004) and include a total of four RCRA groundwater monitoring wells (Figure 4-1). Locations were selected and approved by both CDPHE and EPA. Of these, one is upgradient, and three are downgradient of the Original Landfill.

Upgradient monitoring wells include well P416589. Downgradient monitoring wells include wells 80005, 80105, and 80205. Monitoring well details are summarized in Table 4-1. Boring logs are included in Appendix B.

### **4.4 GROUNDWATER QUALITY SAMPLE PARAMETERS**

Groundwater samples will be submitted for laboratory analysis for the following EPA-approved methods, which were established in the IM/IRA (Kaiser-Hill 2005):

- SW-846 Method 8260B – Volatile Organic Compounds (VOCs)
- SW-846 Method 8081A/8141A – Organochlorine and Organophosphorous Pesticides
- SW-846 Method 6010B – Metals (including uranium)
- SW-846 Method 7470A – Mercury

### **4.5 SAMPLING PROCEDURES SUMMARY**

Groundwater sampling will be conducted in accordance with RFETS Standard Operating Procedures (SOPs). The following sections summarize the groundwater sampling procedures that will be used to monitor groundwater conditions at the Original Landfill. Details include groundwater level measurements, conventional groundwater purging and sampling procedures, quality control (QC) field samples, decontamination procedures, and investigation-derived waste (IDW) management.

#### **4.5.1 Groundwater Level Measurement**

Water levels are measured to determine groundwater flow patterns, water level fluctuations, and the volume of water in a well for the calculation of purge volumes prior to sampling. Since this plan requires measuring water levels from a group of monitoring wells for hydrologic evaluation, such measurements will be conducted as a complete round, separate from any sampling efforts.

The four RCRA monitoring wells will be included during water level measurements. Water levels will be measured in accordance with RFETS SOPs.

#### **4.5.2 Conventional Groundwater Purging and Sampling**

Monitoring wells will be purged before samples are withdrawn to prevent collection of non-representative stagnant water in a well. Well purging will be sufficient to increase the likelihood that the water collected is representative of the groundwater within the formation around the well. All purging and sampling operations will be conducted in accordance with RFETS SOPs.

#### **4.5.3 Quality Control Field Samples**

During implementation of the field sampling program, field quality assurance (QA)/QC samples will be collected to assess the reproducibility of the field collection techniques, the quality of preservation techniques and sample bottles, and the effectiveness of field decontamination procedures. QA/QC procedures are will be conducted in accordance with RFETS SOPs.

#### **4.5.4 Decontamination**

Equipment used in monitoring and sampling must be properly decontaminated. Decontamination must effectively eliminate the potential for cross-contamination between sampling locations and must be conducted using the appropriate materials to prevent the introduction of external contaminants (such as phosphate from detergents, aromatic hydrocarbons from motor vehicles, or oil and grease from dirty hands). Decontamination procedures will be conducted in accordance with RFETS SOPs.

#### **4.5.5 Investigation-Derived Waste (IDW)**

IDW that will accumulate during groundwater monitoring includes decontamination and purge water. Both will be drummed and transported off-site for disposal. The management of IDW will be conducted in accordance with RFETS SOPs.

### **4.6 LABORATORY PROCEDURES SUMMARY**

Analytical methodologies and reporting limits (RLs), data reporting procedures, laboratory QA/QC procedures, laboratory data validation and contractor validation procedures are to be

conducted in accordance with EPA-approved methods. Groundwater samples will be submitted to an EPA-approved analytical laboratory for the analyses listed in Section 4.4.

Prior to implementing procedures, the laboratory will perform an initial demonstration of proficiency as specified in the method. Once the procedure is properly understood by the analyst and acceptable quality control data (precision and accuracy) are achieved, the method is placed in the laboratory for use.

Sample results are reported according to laboratory analytical method SOPs or contract specifications. The laboratory will report any analyte of interest detected at or above the RL as a positive value. Any analyte of interest not detectable or detected below the RL will be reported as "not detected" at the RL or an estimated value between the RL and the instrument or method detection limit. Data are generally reported in a tabular format or posted on maps and figures. RLs are adjusted for dilution when necessary.

#### **4.7 DATA EVALUATION AND REPORTING**

Groundwater monitoring results will be included in the Annual Original Landfill Monitoring Reports discussed in Section 6.0. Groundwater monitoring will be conducted on a quarterly basis at the Original Landfill.

## **5.0 SURFACE WATER MONITORING PLAN**

As part of Original Landfill closure, surface water will be monitored at both upgradient and downgradient locations. This section presents the monitoring plan to determine whether surface water standards are met.


### **5.1 PURPOSE AND REQUIREMENTS**

The Original Landfill surface water monitoring plan has been implemented to determine surface water quality impacts of the landfill (IM/IRA [Kaiser-Hill 2004]). Applicable surface water standards are listed in the RFCA, Attachment 5, Table 1.

As detailed in the IM/IRA, monitoring requirements will consist of quarterly monitoring until the first CERCLA review. A validated exceedance of an effluent limit will trigger monthly monitoring for three consecutive months. Continued exceedances during the three-month period will trigger consultation between the RFCA parties to determine whether a change in the remedy is required, additional parameters need to be analyzed, or a different sampling frequency is required.

### **5.2 DATA QUALITY OBJECTIVES**

Surface water monitoring DQO information can be found in the IMP, Section 2 (Rocky Flats 2005). The following flowchart will be used to guide the decision statement.



### **5.3 SAMPLE LOCATIONS**

Sampling will be conducted at the two locations shown on Figure 4-1, POM5 and POM6. Surface water flow will be manually measured (calibrated bucket and stop watch).

### **5.4 SURFACE WATER SAMPLE PARAMETERS**

Surface water samples will be submitted for laboratory analysis for the following EPA-approved methods, which were established in the IM/IRA:

- SW-846 Method 8260B – VOCs
- SW-846 Method 6010B – Metals (including uranium)
- SW-846 Method 7470A – Mercury

### **5.5 SAMPLING PROCEDURES SUMMARY**

The following sections detail the sampling procedures that will be used to monitor surface water. QC field samples, decontamination procedures, sample identification, and sample handling procedures are identical to those of the groundwater sampling.

#### **Sampling Procedures**

Surface water at the two locations will be sampled by directly placing a collection device or using a pond sampler device. The same collection suite, depending on effluent exceedances, will be taken at each sample location. The pond sampler can be purchased or easily fabricated with the following parts:

- One 250-milliliter (ml) polypropylene beaker (laboratory supply store),
- Adjustable clamp sized for 250-ml beakers (laboratory supply store),
- Aluminum telescoping tube equipped with bolt holes (swimming supply store), and
- Nuts/bolts to attach clamp to telescoping tube (hardware store).

Pond water from the sampler device will be poured directly into the sample containers. The device must be decontaminated in accordance with Section 4.5.4 between samples.

## **5.6 LABORATORY PROCEDURES SUMMARY**

Analytical methodologies and RLs, data reporting procedures, laboratory QA/QC procedures, and laboratory data validation and contractor validation procedures are similar to those for groundwater sampling provided in Section 4.6.

## **5.7 REPORTING AND SCHEDULING**

Surface water sampling results will be included in the Annual Original Landfill Monitoring Reports discussed in Section 6.0. Surface water monitoring will be conducted on a quarterly basis at the Original Landfill.

## **6.0 REPORTING AND CONTACT INFORMATION**

### **6.1 REPORTING**

The complete Annual Original Landfill Monitoring Report, including inspection results, repairs, groundwater monitoring data, and surface water monitoring data if applicable, will be submitted to the RFCA parties. Any maintenance action activities will be detailed in the report. If conditions appear that are of concern and require immediate attention, the RFCA parties will be notified immediately. The Annual Original Landfill Monitoring Report will include at a minimum:

- Monthly vegetation inspection forms for the first two growing seasons;
- Quarterly inspection forms;
- Notations of problems, maintenance action(s) taken, and maintenance or repairs as a result of the quarterly inspection;
- Any deviations from the Landfill Monitoring and Maintenance Plan and the rationale for such deviations;
- Summary of monitoring locations;
- Tables with depth to water, well elevations, and groundwater elevations;
- Table with groundwater results and associated qualifiers;
- Tables with surface water results and associated qualifiers;
- Figures with groundwater monitoring points and location(s) of problems and/or repairs; and
- Groundwater and surface water sampling forms.

### **6.2 CONTACT INFORMATION**

The point of contact and contact information for the Original Landfill during the monitoring and maintenance phase is as follows:

Scott Surovchak/Department of Energy  
Rocky Flats Project Office  
12101 Airport Way, Unit A  
Broomfield, CO 80021-2583  
303-966-3551



## 7.0 REFERENCES

- Earth Tech, Inc. 2005. *Final Design Analysis, Accelerated Action Design for the Original Landfill*. May.
- EG&G. 1994. *Technical Memorandum No. 15, Addendum to Final Phase I RFI/RI Work Plan, Amended Field Sampling Plan, Volume 2, Woman Creek Priority Drainage, Rocky Flats Plant, Golden, Colorado*. May.
- Kaiser-Hill Company, L.L.C. 2005. *Final Interim Measure/Interim Remedial Action for the Original Landfill*. March.
- Rockwell. 1988. *Remedial Investigation and Feasibility Study Plans for Low Priority Sites, Volume I – Site Descriptions, Groupings and Prioritization*. June.
- Rocky Flats. 2005. *RFETS Integrated Monitoring Plan FY2005, Revision 1, Background Document*. September.

**TABLE 4-1**  
**GROUNDWATER MONITORING WELLS**  
**PRESENT LANDFILL**  
**1 OF 1**

Well ID	Type	Installation Date	Screen Length (feet)	Borehole Depth (feet bgs)	Well Diameter (inches)	Depth to Top of Screen (feet bgs)	Depth to Bedrock (feet bgs)
70193	Upgradient	1/15/93	15	39.4	2	22.30	19.50
70393	Upgradient	2/2/93	15	26.0	2	7.80	22.80
70693	Upgradient	12/4/92	20	30.3	2	8.50	28.50
73005	Downgradient	6/27/05	20	28.0	2	4.60	0.00
73105	Downgradient	6/27/05	20	27.7	2	5.65	12.50
73205	Downgradient	6/27/05	25	32.0	2	4.55	4.20

Notes:

bgs

below ground surface

**TABLE 4-2**  
**GROUNDWATER SAMPLING PARAMETERS**  
**PRESENT LANDFILL**  
**1 OF 3**

Parameter ID	Parameter Name
<b>ORGANICS</b>	
	<i>Volatile Organic Compounds</i>
67-64-1	Acetone
71-43-2	Benzene
108-86-1	Bromobenzene
74-97-5	Bromochloromethane
75-27-4	Bromodichloromethane
75-25-2	Bromoform
74-83-9	Bromomethane
78-93-3	2-Butanone (MEK)
104-51-8	n-Butylbenzene
135-98-8	sec-Butylbenzene
98-06-6	tert-Butylbenzene
75-15-0	Carbon Disulfide
56-23-5	Carbon Tetrachloride
108-90-7	Chlorobenzene
75-00-3	Chloroethane
67-66-3	Chloroform
74-87-3	Chloromethane
95-49-8	2-Chlorotoluene
106-43-4	4-Chlorotoluene
96-12-8	1,2-Dibromo-3-chloropropane
124-48-1	Dibromochloromethane
106-93-4	1,2-Dibromomethane (EDB)
74-95-3	Dibromomethane
95-50-1	1,2-Dichlorobenzene
541-73-1	1,3-Dichlorobenzene
106-46-7	1,4-Dichlorobenzene
75-71-8	Dichlorodifluoromethane
75-34-3	1,1-Dichloroethane
107-06-2	1,2-Dichloroethane
75-35-4	1,1-Dichloroethylene
156-59-2	cis-1,2-Dichloroethylene
156-60-5	trans-1,2-Dichloroethylene
78-87-5	1,2-Dichloropropane
142-28-9	1,3-Dichloropropane
594-20-7	2,2-Dichloropropane
563-58-6	1,1-Dichloropropene
10061-01-5	cis-1,3-Dichloropropene
10061-02-6	trans-1,3-Dichloropropene

**TABLE 4-2**  
**GROUNDWATER SAMPLING PARAMETERS**  
**PRESENT LANDFILL**  
**2 OF 3**

Parameter ID	Parameter Name
100-41-4	Ethyl Benzene
87-68-3	Hexachlorobutadiene
591-78-6	2-Hexanone
98-82-8	Isopropylbenzene
99-87-6	p-Isopropyltoluene
108-10-1	4-Methyl-2-pentanone (MIBK)
75-09-2	Methylene Chloride
91-20-3	Napthalene
103-65-1	n-Propylbenzene
100-42-5	Styrene
630-20-6	1,1,1,2-Tetrachloroethane
79-34-5	1,1,2,2-Tetrachloroethane
127-18-4	Tetrachloroethylene
108-88-3	Toluene
87-61-6	1,2,3-Trichlorobenzene
120-82-1	1,2,4-Trichlorobenzene
71-55-6	1,1,1-Trichloroethane
79-00-5	1,1,2-Trichloroethane
79-01-6	Trichloroethylene
75-69-4	Trichlorofluoromethane
96-18-4	1,2,3-Trichloropropane
76-13-1	1,1,2-Trichlorotrifluoroethane
95-63-6	1,2,4-Trimethylbenzene
108-67-8	1,3,5-Trimethylbenzene
75-01-4	Vinyl Chloride
1330-20-7	Xylenes
<b>INORGANICS</b>	
<i>Pesticides</i>	
57-74-9	Chordone
72-20-8	Endrin
76-44-8	Heptachlor
58-89-9	Lindane
72-43-5	Methoxychlor
800-135-2	Toxaphene
<i>Metals</i>	
7429-90-5	Aluminum
7440-36-0	Antimony
7440-38-2	Arsenic
7440-39-3	Barium
7440-41-7	Beryllium
7440-43-9	Cadmium

**TABLE 4-2**  
**GROUNDWATER SAMPLING PARAMETERS**  
**PRESENT LANDFILL**  
**3 OF 3**

<b>Parameter ID</b>	<b>Parameter Name</b>
7440-70-2	Calcium
7440-47-3	Chromium
7440-48-4	Cobalt
7440-50-8	Copper
7439-89-6	Iron
7439-92-1	Lead
7439-93-2	Lithium
7439-95-4	Magnesium
7439-96-5	Manganese
7439-97-6	Mercury
7439-98-7	Molybdenum
7440-02-0	Nickel
7440-09-7	Potassium
7782-49-2	Selenium
7440-22-4	Silver
7440-23-5	Sodium
7440-24-6	Strontium
7440-28-0	Thallium
7440-31-5	Tin
11-09-6	Uranium
7440-62-2	Vanadium
7440-66-6	Zinc

## FIGURES

DATE: 12/8/2004

CAD FILE: GROUP\CAD\ROCKY\_FLATS\NEWDESIGN\_2004\PLFINAL\LOCATION.DGN




FIGURE 1-1

LOCATION MAP

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE  
GOLDEN, COLORADO









FIGURE 1-2

ORIGINAL LANDFILL SITE MAP

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE  
GOLDEN, COLORADO








**LEGEND**  
 - - - DIVERSION BERM  
 <- CHANNEL  
 - - - LIMIT OF WASTE




**FIGURE 2-1**  
**ORIGINAL LANDFILL COVER**  
 ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE  
 GOLDEN, COLORADO



NOTE: IN AREAS OUTSIDE OF THE WASTE FOOTPRINT, COVER SOIL MAY BE LESS THAN 2' ON TRANSITION AREAS OR NO COVER SOIL.


### DIVERSION BERM (SECTION)

NTS



### PERMANENT/GRASS-LINED CHANNEL DETAIL (SECTION)


NTS



NOTE: IN AREAS OUTSIDE OF THE WASTE FOOTPRINT, COVER SOIL MAY BE LESS THAN 2' ON TRANSITION AREAS OR NO COVER SOIL.


### DOWNSLOPE CHANNEL TRANSITION FROM DIVERSION BERM TO CHANNEL (PLAN VIEW)

NTS



### END CHANNEL (PLAN VIEW)

NTS



# **Legend**

- Groundwater monitoring well
- ▲ Surface water monitoring location

--- Waste material boundary

## **Standard Map Features**

- Lake or pond
- Stream, ditch, or other drainage feature
- Paved road
- Dirt road
- Trail
- Fence
- Topographic contour (20 foot)

FIGURE 4-1

ORIGINAL LANDFILL GROUNDWATER AND  
SURFACE WATER MONITORING  
ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE  
GOLDEN, COLORADO

EARTH  TECH

**APPENDIX A**

**ORIGINAL LANDFILL – MONITORING AND MAINTENANCE PROGRAM  
INSPECTION FORM**

# ORIGINAL LANDFILL – MONITORING AND MAINTENANCE PROGRAM

## INSPECTION FORM

INSPECTOR: \_\_\_\_\_ DATE: \_\_\_\_\_

TEMPERATURE: \_\_\_\_\_ WEATHER CONDITIONS: \_\_\_\_\_

### SUBSIDENCE / CONSOLIDATION

REGION	EVIDENCE OF CRACKS?	EVIDENCE OF DEPRESSIONS?	EVIDENCE OF SINK HOLES?	OTHER (DESCRIBE BELOW)
COVER – WEST	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
COVER – EAST	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
BUTTRESS FILL	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
DIVERSION BERM 1	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
DIVERSION BERM 2	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
DIVERSION BERM 3	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
DIVERSION BERM 4	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
DIVERSION BERM 5	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
DIVERSION BERM 6	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
DIVERSION BERM 7	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	

MAINTENANCE REQUIRED / COMMENTS

---



---



---

## SLOPE STABILITY

REGION	EVIDENCE OF SEEPS?	EVIDENCE OF BLOCK OR CIRCULAR FAILURE?	EVIDENCE OF BLOCK OR CIRCULAR FAILURE?
COVER – WEST	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
COVER – EAST	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
BUTTRESS FILL SIDESLOPE	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
WEST PERIMETER CHANNEL SIDESLOPES	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
EAST PERIMETER CHANNEL SIDESLOPES	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
COVER SEEPS (IF PRESENT)	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	

MAINTENANCE REQUIRED / COMMENTS

---



---



---



---

## SOIL COVER

REGION	EVIDENCE OF SOIL DEPOSITION OR EROSION?	EVIDENCE OF EROSION RILLS/GULLIES?	EVIDENCE OF BURROWING ANIMALS?	OTHER (DESCRIBE BELOW)
COVER - WEST	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
COVER - EAST	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
BUTTRESS FILL	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
BUTTRESS FILL SIDESLOPE	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	

MAINTENANCE REQUIRED / COMMENTS

---



---



---



---

## VEGETATION

REGION	CONDITION OF GRASS	UNWANTED VEGETATION PRESENT*?	PERCENTAGE OF GRASS VERSUS BARE GROUND?	PERCENTAGE OF UNWANTED VEGETATION?
COVER- WEST		<input type="checkbox"/> Yes <input type="checkbox"/> No		
COVER - EAST		<input type="checkbox"/> Yes <input type="checkbox"/> No		
DIVERSION BERM 1		<input type="checkbox"/> Yes <input type="checkbox"/> No		
DIVERSION BERM 2		<input type="checkbox"/> Yes <input type="checkbox"/> No		
DIVERSION BERM 3		<input type="checkbox"/> Yes <input type="checkbox"/> No		
DIVERSION BERM 4		<input type="checkbox"/> Yes <input type="checkbox"/> No		
DIVERSION BERM 5		<input type="checkbox"/> Yes <input type="checkbox"/> No		
DIVERSION BERM 6		<input type="checkbox"/> Yes <input type="checkbox"/> No		
DIVERSION BERM 7		<input type="checkbox"/> Yes <input type="checkbox"/> No		
WEST PERIMETER CHANNEL		<input type="checkbox"/> Yes <input type="checkbox"/> No		
EAST PERIMETER CHANNEL		<input type="checkbox"/> Yes <input type="checkbox"/> No		
UPPER BUTTERESS FILL SIDESLOPE		<input type="checkbox"/> Yes <input type="checkbox"/> No		
LOWER BUTTRESS FILL SIDESLPOE		<input type="checkbox"/> Yes <input type="checkbox"/> No		

\* Unwanted vegetation includes weeds and deep-rooting trees.

MAINTENANCE REQUIRED / COMMENTS

---



---



---



---



# STORMWATER MANAGEMENT STRUCTURES

## CHANNELS / LINING

STRUCTURE	EVIDENCE OF EXCESSIVE EROSION, GULLYING, SCOUR, OR UNDERMINING?	EVIDENCE OF SETTLEMENT/ SUBSIDENCE OR DEPRESSIONS?	EVIDENCE OF BREACHING OR BANK FAILURE?	EVIDENCE OF BURROWING ANIMALS?	EVIDENCE OF SEDIMENT BUILD-UP OR OTHER BLOCKAGE?	EVIDENCE OF LINING DETERIORATION, HOLES, RIPS, OR SEPARATION?	EVIDENCE OF LINING DISPLACEMENT?
DIVERSION BERM 1	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
DIVERSION BERM 2	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
DIVERSION BERM 3	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
DIVERSION BERM 4	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
DIVERSION BERM 5	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
DIVERSION BERM 6	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
DIVERSION BERM 7	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
CHECK DAMS	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
WEST PERIMETER CHANNEL	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No
EAST PERIMETER CHANNEL	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No

OTHER DEFICIENCIES?

MAINTENANCE REQUIRED / COMMENTS

# **STORMWATER MANAGEMENT STRUCTURES (CONTINUED)**

## **OUTFALLS**

CHECK EACH STRUCTURE FOR EXCESSIVE EROSION AND SEDIMENT DEPTH. IF SEDIMENT DEPTH IS COMPROMISING THE DESIGN CHARACTERISTICS, REMOVE SEDIMENT.

STRUCTURE	CONDITION / SEDIMENT DEPTH
DIVERSION BERM OUTFALL 1	
DIVERSION BERM OUTFALL 2	
DIVERSION BERM OUTFALL 3	
DIVERSION BERM OUTFALL 4	
DIVERSION BERM OUTFALL 5	
DIVERSION BERM OUTFALL 6	
DIVERSION BERM OUTFALL 7	
WEST PERIMETER CHANNEL OUTFALL	
EAST PERIMETER CHANNEL OUTFALL	
FRENCH DRAIN OUTFALL (SID)	

OTHER DEFICIENCIES?

---



---

MAINTENANCE REQUIRED / COMMENTS

---



---

## EROSION CONTROL

AREA		ADVERSELY AFFECTING OLF?	
NORTH OF THE ORIGINAL LANDFILL	<input type="checkbox"/> Yes <input type="checkbox"/> No		COMMENT:
WEST OF THE WEST PERIMETER CHANNEL	<input type="checkbox"/> Yes <input type="checkbox"/> No		COMMENT:
EAST OF THE EAST PERIMETER CHANNEL	<input type="checkbox"/> Yes <input type="checkbox"/> No		COMMENT:
NORTH OF WOMAN CREEK	<input type="checkbox"/> Yes <input type="checkbox"/> No		COMMENT:

MAINTENANCE REQUIRED

---



---



---



---

# **INSTITUTIONAL CONTROLS**

ITEM		
EVIDENCE OF EXCAVATION(S) OF COVER AND IMMEDIATE VICINITY OF COVER?	<input type="checkbox"/> Yes <input type="checkbox"/> No	COMMENT:
EVIDENCE OF CONSTRUCTION OF ROADS, TRAILS ON COVER OR BUILDINGS?	<input type="checkbox"/> Yes <input type="checkbox"/> No	COMMENT:
EVIDENCE OF DRILLING OF WELLS OR USE OF GROUNDWATER?	<input type="checkbox"/> Yes <input type="checkbox"/> No	COMMENT:
DAMAGE OR REMOVAL OF ANY SIGNAGE OR GROUNDWATER MONITORING WELLS?	<input type="checkbox"/> Yes <input type="checkbox"/> No	COMMENT:

OTHER DEFICIENCIES?

---



---



---



---

## ACTION ITEMS

[illegible]

SIGNATURE: \_\_\_\_\_ DATE: \_\_\_\_\_

L:\work\57378\Work\Product\OLF\M & M Plan - Final\Appendix A\Final Inspection Report.doc

**DIVERSION BERMS 1,2,3,4,5,6,7**  
 SLOPE: 2%  
 SHAPE: TRIANGULAR  
 HEIGHT: 3 FEET  
 PERMANENT LINING: GRASS  
 TEMPORARY LINING: C125 AND C125BN EROSION MAT

**EAST CHANNEL**  
 SLOPE: 12%  
 SHAPE: TRAPEZOIDAL-18 FOOT BOTTOM  
 SIDESLOPES: 3:1 TO 4:1  
 MINIMUM DEPTH: 2 FEET  
 PERMANENT LINING: NAG P550

**WEST CHANNEL**  
 SLOPE: 12%  
 SHAPE: TRAPEZOIDAL-10 FOOT BOTTOM  
 SIDESLOPES: 3:1  
 MINIMUM DEPTH: 2 FEET  
 PERMANENT LINING:  
 NAG P550

LIMIT OF WASTE (TYP)

DIVERSION BERM 1

DIVERSION BERM 2

DIVERSION BERM 3

DIVERSION BERM 4

DIVERSION BERM 5

DIVERSION BERM 6

DIVERSION BERM 7

COVER WEST

COVER EAST

DOWNSLOPE CHANNEL (TYP)

BUTTRESS FILL  
 AND SIDESLOPE

80005

80105


80205

**LEGEND**

- DIVERSION BERM
- - - CHANNEL
- - - LIMIT OF WASTE
- GROUNDWATER MONITORING WELL

EARTH  TECH

ORIGINAL LANDFILL INSPECTIONS  
 ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE  
 GOLDEN, COLORADO



**APPENDIX B**

**GROUNDWATER WELL BORING LOGS / CONSTRUCTION SUMMARIES**

STATE PLANE COORDINATE:

NORTH: 74211

EAST: 2081546

REMARKS: Hollow Stem Auger, Weston Log.

TOTAL DEPTH (FT): 36.5

AREA: PLANT

LOCATOR NUMBER: 18

GROUND ELEVATION (FT): 6041.20

CASING DIAMETER (IN): 2-3/8 O.D.

BOREHOLE DIAMETER (IN): 1.25

OLD WELL NUMBER: P260-89

GEOLOGIST: SPC

DATE DRILLED: 09/14/88

LOG OF BORDING NUMBER:

P416589

SAMPLE NUMBER

SAMPLE GRAIN SIZE

PERCENT RECOVERY

RECOVERY INTERVAL

DATE (FT) DEPTH (FT)

WELL OR PIECE OF CONSTRUCTION

LITHOLOGY

UNITED SOILS CLASSIFICATION OR ROCK TYPE

DESCRIPTION

500002

500003

500004

500005

500006

500007

2.00 / 2.00

1.00 / 2.00

1.00 / 2.00

1.20 / 2.00

0.00 / 2.00

6041

6040

6039

6038

6037

6036

6035

6034

6033

6032

6031

6030

6029

6028

6027

6026

6025

6024

6023

6022

6021

6020

6019

6018

6017

6016

6015

6014

6013

6012

6011

6010

6009

6008

6007

6006

6005

6004

6003

6002

6001

6000

5999

5998

5997

5996

5995

5994

5993

5992

5991

5990

5989

5988

5987

5986

5985

5984

5983

5982

5981

5980

5979

5978

5977

5976

5975

5974

5973

5972

5971

5970

5969

5968

5967

5966

5965

5964

5963

5962

5961

5960

5959

5958

5957

5956

5955

5954

5953

5952

5951

5950

5949

5948

5947

5946

5945

5944

5943

5942

5941

5940

5939

5938

5937

5936

5935

5934

5933

5932

5931

5930

5929

5928

5927

5926

5925

5924

5923

5922

5921

5920

5919

5918

5917

5916

5915

5914

5913

5912

5911

5910

5909

5908

5907

5906

5905

5904

5903

5902

5901

5900

5899

5898

5897

5896

5895

5894

5893

5892

5891

5890

5889

5888

5887

5886

5885

5884

5883

5882

5881

5880

5879

5878

5877

5876

5875

5874

5873

5872

5871

5870

5869

5868

5867

5866

5865

5864

5863

5862

5861

5860

5859

5858

5857

5856

5855

5854

5853

5852

5851

5850

5849

5848

5847

5846

5845

5844

5843

5842

5841

5840

5839

5838

5837

5836

5835

5834

5833

5832

5831

5830

5829

5828

5827

5826

5825

5824

5823

5822

5821

5820

5819

5818

5817

5816

5815

5814

5813

5812

5811

5810

5809

5808

5807

5806

5805

5804

5803

5802

5801

5800

5799

5798

5797

5796

5795

5794

5793

5792

5791

5790

5789

5788

5787

5786

5785

5784

5783

5782

5781

5780

5779

5778

5777

5776

5775

5774

5773

5772

5771

5770

5769

5768

5767

5766

5765

5764

5763

5762

5761

5760

5759

5758

5757

5756

5755

5754

5753

5752

5751

5750

5749

5748

5747

5746

5745

5744

5743

5742

5741

5740

5739

5738

5737

5736

5735

5734



MULTI-METER WELL LOG

STATE PLANE COORDINATE:		TOTAL DEPTH (FT): 36.5	GROUND ELEVATION (FT): 6041.20	OLD WELL NUMBER: P260-89	LOG OF BORING NUMBER:
NORTH: 748211	AREA: PLANT	CASTING DIAMETER (IN): 2-3/8 O.D.	GEOLOGIST: SPC	P416589	
EAST: 2081546	LOCATOR NUMBER: 18	BOREHOLE DIAMETER (IN): 1.25	DATE DROLLED: 09/14/89		
REMARKS: Hollow Stem Auger. Weston Log.					

SAMPLE NUMBER	SAMPLE GRAIN SIZE	PERCENT RECOVERY	RECOVERY INTERVAL	DATE (FT) DEPTH (FT)	WELL OR PIEZOMETER CONSTRUCTION	LITHOLOGY	UNITED SOILS CLASSIFICATION OR ROCK TYPE	DESCRIPTION
				10 6051			SC:	Gravelly Clayey Sand - same as above, as indicated by cuttings.
				11 6050			SC:	Gravelly Clayey Sand - same as above, as indicated by cuttings.
76091214				12 6029			SC:	Gravelly Clayey Sand - banded, varicolored, mod. red (5 R 5/4), pale reddish brown (10 R 5/4), light brown (5 YR 5/6), dark yellowish orange (10 YR 6/6), yellowish gray (5 Y 7/2), non-stratified f.g. to v.c.g. sand, some gravel, some silt, poor sorting, sub-angular, quartzose. Low plasticity, iron staining, calcareous. 0.5 cm. lense of Silty Clay, dense to med. dense, damp.
76091216				13 6028				
				14 6027			SC:	Gravelly Clayey Sand - same as above, with scattered cobbles.
76091115				15 6026			NO SAMPLE:	NO SAMPLE.
				16 6025			SC:	Gravelly Clayey Sand - same as above. Increased clay content
76091618				17 6024				
76091620				18 6023			SH:	Gravelly Silty Sand - same as above. Light brown (5 YR 5/6), light olive gray (5 Y 6/1). Some clay, quartzose.
76091820				19 6022				


STATE PLANE COORDINATE:  
 NORTH: 748211  
 EAST: 208156  
 REMARKS: Hollow Stem Auger. Weston Log.

TOTAL DEPTH (FT): 36.5  
 AREA: PLANT  
 LOCATOR NUMBER: 18

GROUND ELEVATION (FT): 6041.20  
 CASING DIAMETER (IN): 2-3/8 O.D.  
 BOREHOLE DIAMETER (IN): 1.25

OLD WELL NUMBER: P260-89  
 GEOLOGIST: SPC  
 DATE DROLLED: 09/14/89

LOG OF BORING NUMBER:  
**P416589**




STATE PLANE COORDINATE:  
 NORTH: 748211  
 EAST: 2081546  
 REMARKS: Hollow Stem Auger, Weston Log.

TOTAL DEPTH (FT): 36.5  
 AREA: PLANT  
 LOCATOR NUMBER: 18

GROUND ELEVATION (FT): 6041.20  
 CASING DIAMETER (IN): 2-3/8 O.D.  
 BOREHOLE DIAMETER (IN): 7.25

OLD WELL NUMBER: P760-89  
 GEOLOGIST: SPC  
 DATE DROLLED: 09/14/89

LOG OF BORING NUMBER:  
**P416589**




STATE PLANE COORDINATES AREA: GRND ELEV. (FT): 5957.54  
 NORTH: 747489.979 TOTAL DEPTH (FT): 21.0  
 EAST: 2081404.042 COMPLETION DATE: 8/9/05  
 PROJECT: Original Landfill GEOLOGIST: E. Warp  
 REMARKS:  
 Routine well installation

CASING DIA (IN): 2"  
 BH DIA. (IN): 8"  
 GRID LOCATOR:

LOG OF BORING NUMBER:  
**80005**


Page 1 of 3



Elev (Ft)	Well or Piezometer Construction and Materials	Depth (Ft)	Lithology	Unified Soils Classification or Rock Type	LOG OF BORING NUMBER: <b>80005</b> Lithologic Description	Page 2 of 3
-----------	---	------------	-----------	---	---	-------------

5952		5		subangular to subrounded). Clay has medium plasticity. Moist. Shattered cobbles (1" - 2" diameter) at base of interval from 4.6' to 4.8'.
5951		6		SC/CL: Silty, Sandy Clay with some gravel, brown (7.5YR4/3 to 7.5YR4/4). Sand and gravel increase at base of interval. ~35% sand from 5.1' to 5.4', sand is coarse grained, subangular. ~25% gravel (1/4" - 1/2" diameter, subangular) from 5.1' to 5.4'. Moist. Possibly fluvial in origin (?)
5950		7		No recovery.
5949		8		SC/CL: Silty, Sandy Clay with some gravel, same as interval from 4.8' to 5.4'. Moist.
5948		9		SILTSTONE: TOP OF BEDROCK. Clayey Siltstone with some fine grained sand. Bedrock is gray (10YR6/1) with abundant yellowish brown (10YR5/6) mottling. Siltstone interbedded with claystone and fine grained sandy lenses. Some caliche as stringers and blebs throughout interval. Strong pervasive iron oxidation from 8.5' to 8.7' with ironstone fragments. Moist.
5947		10		SILTSTONE: Sandy Siltstone, grayish brown (10YR5/2) with light yellowish brown (10YR6/4) iron oxidation mottled throughout. Abundant very fine grained sand in siltstone. Friable. Caliche along internal bedding at 10.7'. Decreasing moisture to slightly moist.
5946		11		SILTSTONE: Clayey, Sandy Siltstone, yellowish brown (10YR5/6) with gray (10YR6/1) and light brownish gray (10YR6/2) mottling. Clayey lenses at 10.9' and from 11.65' to 11.8'. Black organic stringers associated with clayey lenses. Interval is friable and slightly fissile. Rip-up clasts common. Small healed fracture (45 deg) with iron oxidation at 11.95'. Abundant very fine grained sand from 11.2' to 11.4'. Slightly moist.
5945		12		SILTSTONE: Clayey Siltstone, yellowish brown (10YR5/6) with gray (10YR5/1) mottling from 12.4' to 13.0'. Color changes to brown (10YR5/3) from 13.0' to 14.0'. Decreasing very fine grained sand to trace. Black organic stringers common from 13.0' to 14.0'. Interval is competent, yet weak to moderately friable. Rip-up clasts common. Weak to moderate iron oxidation throughout. Slightly moist.
5944		13		

Elev (Ft)	Well or Piezometer Construction and Materials	Depth (Ft)	Lithology	Unified Soils Classification or Rock Type	Lithologic Description	LOG OF BORING NUMBER: <b>80005</b>	Page 3 of 3
-----------	--	------------	-----------	---	------------------------	---------------------------------------	-------------



STATE PLANE COORDINATES AREA: GRND ELEV. (FT): 5939.29  
 NORTH: 747463.414  
 EAST: 2081942.494  
 PROJECT: Original Landfill  
 REMARKS:  
 Routine well installation

TOTAL DEPTH (FT): 20.15  
 COMPLETION DATE: 8/8/05  
 GEOLOGIST: E. Warp


CASING DIA (IN): 2"  
 BH DIA. (IN): 8"  
 GRID LOCATOR:

LOG OF BORING NUMBER:  
**80105**

Page 1 of 3


Elev (Ft)	Well or Piezometer Construction and Materials	Depth (Ft)	Lithology	Unified Soils Classification or Rock Type	Lithologic Description
5942		3	Protective Casing, Steel, 6 in. ID.		
			Casing, Sch 40-PVC, 2 in. ID.		
5941		2			
		1			
5940		0			
5939		1			GC/CL: Gravel/Sandy Clay with silt mixture. Imported Qalrf fill. Strong brown (7.5YR4/6). 20 - 25% gravel (1/8" - 1" diameter, subrounded to subangular), predominately quartzite with less schist and granite. 20% sand (coarse grained, subangular to subrounded). Clay has medium plasticity. Dark brown (7.5YR3/2) clay lense from 0.4' to 0.5'. Disseminated caliche, tiny white specks common throughout interval. Moist.
5938		2			No recovery.
5937		3			GC/CL: Gravel/Sandy Clay with silt mixture, same as interval from 0.0' to 1.2'. Moist.
		4			No recovery
5936			Hydrated Bentonite Chips		
5935			Filter Pack, 15/40 Silica Sand		CL: Gravelly, Sandy Clay, dark brown (7.5YR3/2). Distinct color change. ~10% sand (coarse grained, subangular), 5 - 8% gravel (1/8" - 1/2" diameter, subrounded to subangular). Trace to some

Elev (Ft)	Well or Piezometer Construction and Materials	Depth (Ft)	Lithology	Unified Soils Classification or Rock Type	LOG OF BORING NUMBER: <b>80105</b> Lithologic Description	Page 2 of 3
-----------	---	------------	-----------	---	---	-------------





Elev (Ft)	Well or Piezometer Construction and Materials	Depth (Ft)	Lithology	Unified Soils Classification or Rock Type	LOG OF BORING NUMBER: <b>80105</b>	Lithologic Description	Page 3 of 3
-----------	---	------------	-----------	---	---------------------------------------	------------------------	-------------




STATE PLANE COORDINATES AREA: GRND ELEV. (FT): 5938.52  
 NORTH: 747535.636 TOTAL DEPTH (FT): 20.0  
 EAST: 2082324.443 COMPLETION DATE: 8/10/05  
 PROJECT: Original Landfill GEOLOGIST: E. Warp  
 REMARKS:  
 Routine well installation


CASING DIA (IN): 2"  
 BH DIA. (IN): 8"  
 GRID LOCATOR:

LOG OF BORING NUMBER:  
**80205**


Page 1 of 3



Elev (Ft)	Well or Piezometer Construction and Materials	Depth (Ft)	Lithology	Unified Soils Classification or Rock Type	LOG OF BORING NUMBER: <b>80205</b>	Lithologic Description	Page 2 of 3
-----------	---	------------	-----------	---	---------------------------------------	------------------------	-------------



Elev (Ft)	Well or Piezometer Construction and Materials	Depth (Ft)	Lithology	Unified Soils Classification or Rock Type	LOG OF BORING NUMBER: <b>80205</b> Lithologic Description	Page 3 of 3
-----------	---	------------	-----------	---	---	-------------



CLAYSTONE: Claystone, gray (10YR5/1) to dark gray (10YR4/1). Massive textured. Trace iron oxidation along bedding planes (sub-horizontal). Disseminated caliche coating from 15.2' to 15.8' along vertical fracture with iron oxidation. Interval weakly friable. Trace black organic stringers. Decreased moisture to trace.

CLAYSTONE: Claystone, dark gray (10YR4/1) to very dark gray (10YR3/1). Massive texture. Moderately fissile and friable. No iron oxidation. Trace moisture to dry.

## **APPENDIX C**

### **RFETS SOPs**